



Phase 2 Report

Prepared by:
URS Corporation/Jack R. Benjamin & Associates, Inc.

Prepared for:
California Department of Water Resources (DWR)

June, 2011

TABLE OF CONTENTS

Section 1	Introduction.....	1-1
1.1	Purpose.....	1-1
1.1.1	Assembly Bill 1200	1-1
1.1.2	Goals and Objectives	1-2
1.2	Risk Analysis Summary.....	1-3
1.3	Phase 2 Evaluation	1-3
1.4	Project Team.....	1-4
1.4.1	Project Sponsors	1-4
1.4.2	Steering Committee	1-4
1.4.3	Technical Advisory Committee	1-4
1.4.4	DRMS Consulting Team.....	1-5
1.4.5	Risk Resources Group	1-6
1.5	Relationship to Other Initiatives	1-6
1.5.1	Delta Vision	1-6
1.5.2	Bay-Delta Conservation Plan.....	1-7
1.5.3	CALFED End of Stage 1	1-7
1.5.4	Other Initiatives	1-8
1.6	Report Organization	1-8
Section 2	Building Blocks and Scenarios	2-1
2.1	Building Block and scenario identification	2-1
2.2	Building Blocks.....	2-1
2.3	Scenarios.....	2-2
Section 3	Building Block 1.1: Improved Delta Levee Maintenance.....	3-1
3.1	Introduction	3-1
3.1.1	Background	3-1
3.1.2	Purpose and Scope of Building Block	3-2
3.1.3	Objective and Approach.....	3-3
3.2	Conceptual Development of Improvement.....	3-3
3.2.1	Analysis Criteria and Basis of Design.....	3-3
3.2.2	Analysis Results.....	3-4
3.2.3	Description of Values, Benefits, and Constraints	3-4
3.3	Cost Estimates	3-4
3.4	Risk Reduction Estimate.....	3-5
3.4.1	Direct Risk Reduction	3-5
3.4.2	Estimation of Risk Reduction	3-5
3.5	Findings and Conclusions	3-6
Section 4	Building Block 1.2: Upgraded Delta Levees	4-1
4.1	Introduction	4-1
4.1.1	Background	4-1
4.1.2	Purpose and Scope	4-1

TABLE OF CONTENTS

4.1.3	Objective and Approach.....	4-1
4.2	Description of Improvement.....	4-2
4.2.1	Approach.....	4-2
4.2.2	Select 764 Miles of Levees for Upgrade to PL 84-99 Standards.....	4-2
4.2.3	Select 187 Miles of Levees for Upgrade to UPL Standards.....	4-3
4.2.4	Develop Parametric Upgrade Cross Sections.....	4-3
4.2.5	Assign Site-Specific Parametric Upgrade Cross Sections.....	4-3
4.3	Improvement Costs.....	4-4
4.3.1	Approach.....	4-4
4.3.2	Review of Availability of On-Island Fill Material.....	4-4
4.3.3	Parametric Cross Sections.....	4-4
4.3.4	Cost Estimates of Parametric Cross Sections.....	4-5
4.4	Risk Reduction Estimate.....	4-5
4.4.1	Flood Risk Reduction.....	4-5
4.4.2	Seismic Risk Reduction.....	4-6
4.4.3	Summary of Delta-Wide Risk Reduction Estimates.....	4-6
4.5	Findings.....	4-6
Section 5	Building Block 1.3: Enhanced Emergency Preparedness/Response.....	5-1
5.1	Introduction.....	5-1
5.1.1	Background.....	5-1
5.1.2	Purpose and Scope of Building Block.....	5-2
5.1.3	Objective and Approach.....	5-2
5.2	Conceptual Development of Improvement.....	5-3
5.2.1	Analysis Criteria and Basis of Design.....	5-3
5.2.2	Analysis Results.....	5-3
5.2.3	Description of Improvements.....	5-4
5.3	Cost Estimate.....	5-11
5.4	Risk Reduction Estimate.....	5-11
5.5	Findings and Conclusions.....	5-13
5.5.1	Findings.....	5-13
5.5.2	Conclusions and Recommendations.....	5-13
Section 6	Building Block 1.4: Pre-Flooding of Selected Islands.....	6-1
6.1	Introduction.....	6-1
6.1.1	Background.....	6-1
6.1.2	Purpose and Scope of Building Block.....	6-1
6.1.3	Objective and Approach.....	6-2
6.2	Conceptual Development of Improvement.....	6-3
6.2.1	Analysis Criteria and Basis of Design.....	6-3
6.2.2	Geometric Description of Improvement.....	6-3
6.2.3	Analysis Results.....	6-3
6.2.4	Description of Values, Benefits, and Constraints.....	6-8

TABLE OF CONTENTS

6.3	Cost Estimate	6-8
6.3.1	Capital Cost	6-8
6.3.2	Operation Cost	6-8
6.4	Risk Reduction Estimate	6-8
6.5	Findings and Conclusions	6-9
6.5.1	Findings	6-9
6.5.2	Conclusions and Recommendations	6-9
Section 7	Building Block 1.5: Land Use Changes to Reduce Island Subsidence	7-1
7.1	Introduction	7-1
7.1.1	Background	7-1
7.1.2	Purpose and Scope of Building Block	7-1
7.1.3	Objective and Approach	7-2
7.1.4	Selection of Sites	7-2
7.2	Conceptual Development of Improvement	7-3
7.2.1	Analysis Criteria and Basis of Design	7-3
7.2.2	Analysis Results and Design Layouts (The Engineering and Science That Demonstrates the Feasibility of the Solutions)	7-5
7.2.3	Geometric Description of Improvement (Plates, Drawing, Maps, Cross Sections, Etc.)	7-7
7.2.4	Description of Values, Benefits, and Constraints	7-8
7.3	Cost Estimate	7-11
7.3.1	Construction Considerations	7-11
7.3.2	Cost Estimate Tables (With Variations)	7-12
7.4	Risk Reduction Estimate	7-13
7.4.1	Direct Risk Reduction	7-13
7.4.2	Potential Indirect Risk Reductions In the Context of the Scenarios	7-13
7.5	Findings and Conclusions	7-14
7.5.1	Findings	7-14
7.5.2	Conclusions and Recommendations	7-15
Section 8	Building Block 1.6: Armored “Pathway” (Through-Delta Conveyance)	8-1
8.1	Introduction	8-1
8.1.1	Background	8-1
8.1.2	Purpose and Scope of Building Block	8-1
8.1.3	Objective and Approach	8-1
8.2	Conceptual Development of Improvement	8-2
8.2.1	Analysis Criteria and Basis of Design	8-2
8.2.2	Analysis Results	8-3
8.2.3	Geometric Description of Improvement	8-7
8.2.4	Description of Benefits	8-9
8.3	Cost Estimate	8-11
8.3.1	Item Descriptions	8-11
8.3.2	Cost Estimate Table	8-11

TABLE OF CONTENTS

8.3.3	Cost Resources	8-11
8.3.4	Operation Cost	8-12
8.4	Risk Reduction Estimate.....	8-12
8.5	Findings, Conclusions and Recommendations.....	8-12
Appendix 8A	Environmental Impacts of Building Block 1.6: Armored Pathway	8A-1
8A.1	Introduction	8A-1
8A.1.1	Background	8A-1
8A.1.2	Purpose and Scope of Building Block	8A-3
8A.2	Conceptual Development of Improvement.....	8A-3
8A.2.1	Analysis Criteria and Basis of Design.....	8A-3
8A.2.2	Analysis Results and Design Layouts	8A-5
8A.3	Geometric Design of Improvement.....	8A-8
8A.3.1	Setback Levee Vegetation Design	8A-8
8A.3.2	Description of Benefits and Constraints.....	8A-8
8A.4	Cost Estimate.....	8A-10
8A.4.1	Construction Considerations	8A-10
8A.4.2	Cost Estimate Tables	8A-10
8A.5	Risk Reduction Estimate.....	8A-10
8A.5.1	Discussion of Potential Risk Reduction in the Context of the Scenarios	8A-10
8A.6	Findings and Conclusions	8A-11
8A.6.1	Findings	8A-11
8A.6.2	Conclusions and Recommendations	8A-11
Section 9	Building Block 1.7: Isolated Conveyance Facility Alternatives.....	9-1
9.1	Introduction	9-1
9.1.1	Background	9-1
9.1.2	Purpose and Scope of Building Block	9-2
9.1.3	Objective and Approach.....	9-2
9.2	Conceptual Development of Improvement.....	9-3
9.2.1	Analysis Criteria and Basis of Design.....	9-3
9.2.2	Design.....	9-3
9.2.3	Operations	9-4
9.3	Cost Estimate.....	9-4
9.3.1	Quantities	9-5
9.3.2	Unit Costs.....	9-5
9.3.3	Intake Facilities.....	9-5
9.3.4	Excavation.....	9-5
9.3.5	Canal Embankments	9-6
9.3.6	Bridges.....	9-6
9.3.7	Siphons and Flow Control Structures.....	9-6
9.3.8	Pumping Station.....	9-7

TABLE OF CONTENTS

	9.3.9	Right-of-Way	9-7
	9.3.10	Other Cost Considerations	9-7
9.4		Risk Reduction Estimate.....	9-8
	9.4.1	Water Quality	9-8
	9.4.2	Water Delivery Reliability	9-9
	9.4.3	Water Delivery Efficiency	9-10
	9.4.4	Operational Flexibility	9-10
	9.4.5	Ecosystem Impacts of the Isolated Conveyance Facility	9-10
	9.4.6	Potential Indirect Risk Reductions in the Context of the Scenarios	9-10
9.5		Findings and Conclusions	9-11
Appendix 9A		Ecosystem Impacts of Building Block 1.7: Isolated Conveyance Facility Alternatives.....	9A-1
	9A.1	Ecosystem Impacts of the Isolated Conveyance Facility.....	9A-1
	9A.2	Terrestrial Habitat	9A-1
	9A.3	New Wildlife Areas.....	9A-1
	9A.4	Waterway Obstruction	9A-2
	9A.5	Entrainment in Intake.....	9A-2
	9A.6	Reduction in Intake	9A-4
	9A.7	Benefits, Values, and Constraints	9A-4
		9A.7.1 Benefits and Values	9A-4
		9A.7.2 Constraints.....	9A-5
Appendix 9B		Preliminary Cost Estimate for 15,000 cfs Isolated Conveyance Facility.....	9B-1
Section 10		Building Block 1.8: San Joaquin Bypass	10-1
	10.1	Introduction	10-1
		10.1.1 Background	10-1
		10.1.2 Scope	10-1
		10.1.3 Purpose	10-2
	10.2	Conceptual Development of Improvement.....	10-2
		10.2.1 Description of Current Project Lands, Zoning, and Infrastructure	10-2
		10.2.2 Description of Alternative Projects	10-2
		10.2.3 Analysis Criteria and Basis of Design.....	10-4
		10.2.4 Analysis Results and Design Layouts	10-5
		10.2.5 Geometric Description of Improvement.....	10-6
	10.3	Cost Estimate.....	10-9
	10.4	Findings and Conclusions.....	10-10
		10.4.1 Risk Reduction Estimate	10-10
		10.4.2 Conclusions and Recommendations	10-11

TABLE OF CONTENTS

Section 11	Building Block 2.1: Raise State Highways.....	11-1
11.1	Introduction	11-1
11.1.1	Background	11-1
11.1.2	Purpose and Scope of Building Block	11-1
11.1.3	Objective and Approach	11-1
11.2	Conceptual Development of Improvement.....	11-2
11.2.1	Analysis Criteria and Basis of Design.....	11-2
11.2.2	Analysis Results and Design Layouts	11-3
11.2.3	Geometric Description of Improvement.....	11-3
11.2.4	Description of Values, Benefits, and Constraints	11-3
11.3	Cost Estimate	11-4
11.3.1	Quantities	11-4
11.3.2	Material Source Analysis	11-4
11.3.3	Construction Considerations	11-4
11.3.4	Cost Estimate Tables	11-5
11.4	Risk Reduction Evaluation	11-5
11.4.1	Direct Risk Reduction	11-5
11.4.2	Estimation of Risk Reduction	11-5
11.5	Findings, Conclusions, and Recommendations.....	11-5
Section 12	Building Block 2.2: Armored Infrastructure Corridor	12-1
12.1	Introduction	12-1
12.1.1	Background	12-1
12.1.2	Purpose and Scope of Building Block	12-1
12.1.3	Objective and Approach	12-2
12.2	Conceptual Development of Improvement.....	12-2
12.2.1	Analysis Criteria and Basis of Design.....	12-2
12.2.2	Analysis Results and Design Layouts	12-3
12.2.3	Description of Values, Benefits, and Constraints	12-4
12.3	Cost Estimate.....	12-5
12.3.1	Summary of Quantities.....	12-5
12.3.2	Material Source Analysis	12-5
12.3.3	Construction Considerations	12-5
12.3.4	Cost Estimate Tables	12-5
12.4	Risk Reduction Estimate.....	12-6
12.4.1	Direct Risk Reduction	12-6
12.4.2	Estimation of Risk Reduction	12-6
12.5	Findings, Conclusions, and Recommendations.....	12-7
Section 13	Building Block 3.1: Suisun Marsh Tidal Wetland Restoration and Managed Wetland Enhancements	13-1
13.1	Introduction	13-1
13.1.1	Background: Suisun Marsh and Bay	13-1
13.1.2	Purpose and Scope of Building Block	13-2

TABLE OF CONTENTS

13.2	13.1.3 Objective and Approach	13-2
	13.2 Conceptual Development of Improvement	13-4
	13.2.1 Existing Conditions	13-4
	13.2.2 Selection of Conceptual Restoration Sites	13-4
	13.2.3 Identification of Exterior Levees and Potential Breach Points for Tidal Restoration	13-6
	13.2.4 Identification of Conceptual Areas for Managed Wetlands Enhancement	13-6
	13.2.5 Analysis Results and Design Layouts	13-7
13.3	13.3 Geometric Description of Improvement	13-8
	13.6.1 Assumptions	13-8
	13.3.1 Description of Values, Benefits, and Constraints	13-10
13.4	13.4 Cost Estimate	13-15
13.5	13.5 Risk Reduction	13-16
13.6	13.6 Findings and Conclusions	13-16
	13.6.1 Findings	13-16
	13.6.2 Conclusions and Recommendations	13-17
Section 14	Building Block 3.2: Tidal Marsh Cache Slough Restoration	14-1
14.1	14.1 Introduction	14-1
	14.1.1 Background	14-1
	14.1.2 Purpose and Scope of Building Block	14-1
	14.1.3 Objective and Approach	14-2
14.2	14.2 Conceptual Development of Improvement	14-2
	14.2.1 Analysis Criteria and Basis of Design	14-2
	14.2.2 Analysis Results and Design Layouts	14-8
	14.2.3 Description of Values, Benefits, and Constraints	14-12
14.3	14.3 Cost Estimate	14-15
	14.3.1 Construction Considerations	14-15
	14.3.2 Cost Estimate	14-15
14.4	14.4 Risk Reduction Estimate	14-16
14.5	14.5 Findings and Conclusions	14-16
	14.5.1 Findings	14-16
	14.5.2 Conclusions and Recommendations	14-17
Section 15	Building Block 3.3: Install Fish Screens	15-1
15.1	15.1 Introduction	15-1
	15.1.1 Background	15-1
	15.1.2 Purpose and Scope	15-1
	15.1.3 Objective	15-2
15.2	15.2 Conceptual Development of Improvement	15-2
	15.2.1 Criteria and Basis of Design	15-2
	15.2.2 Isolated Conveyance Intake	15-2
	15.2.3 Banks Pumping Plant Intake	15-5
	15.2.4 Tracy Pumping Plant Intake	15-7

TABLE OF CONTENTS

	15.2.5 Fish Screens for Irrigation Pumping.....	15-10
15.3	Cost Estimate.....	15-14
	15.3.1 Isolated Conveyance Intake	15-14
	15.3.2 Banks Pumping Plant Intake	15-15
	15.3.3 Tracy Pumping Plant Intake.....	15-15
	15.3.4 Fish Screens for Irrigation Pumping.....	15-15
15.4	Risk Reduction Estimate.....	15-16
	15.4.1 Isolated Conveyance Intake	15-16
	15.4.2 Banks Pumping Plant Intake	15-16
	15.4.3 Tracy Pumping Plant Intake.....	15-17
	15.4.4 Fish Screens for Irrigation Pumping.....	15-17
15.5	Findings and Conclusions.....	15-18
	15.5.1 Findings.....	15-18
	15.5.2 Conclusions and Recommendations.....	15-19
Section 16	Building Block 3.4: Setback Levee to Restore Shaded Riverine Habitat.....	16-1
16.1	Introduction	16-1
	16.1.1 Background	16-1
	16.1.2 Purpose and Scope.....	16-1
	16.1.3 Objective and Approach.....	16-1
16.2	Description of Improvement.....	16-1
16.3	Findings	16-2
Section 17	Building Block 3.6: Reduce Water Exports From the Delta.....	17-1
17.1	Introduction	17-1
	17.1.1 Background	17-1
	17.1.2 Purpose and Scope of This Building Block	17-1
	17.1.3 Objective and Approach.....	17-2
17.2	Conceptual Development of Improvement.....	17-2
	17.2.1 Water Use and Economic Effects	17-2
	17.2.2 Water Operations Effects	17-6
	17.2.3 Effects on Aquatic Species.....	17-8
17.3	Impact Estimates: Non-Breach Conditions	17-10
	17.3.1 Urban Water Agencies	17-10
	17.3.2 Agricultural Water Agencies	17-10
	17.3.3 State and Federal Project Operations	17-10
	17.3.4 Aquatic Ecosystem Impacts	17-11
17.4	Risk Reduction Estimate.....	17-11
	17.4.1 Urban Water Agencies	17-11
	17.4.2 Agricultural Water Users	17-11
	17.4.3 Aquatic Ecosystem	17-12
17.5	Findings and Conclusions.....	17-12
	17.5.1 Findings.....	17-12
	17.5.2 Conclusions and Recommendations.....	17-13

TABLE OF CONTENTS

Section 18	Scenario Evaluation.....	18-1
18.1	Scenario Evaluation	18-1
18.2	Trial Scenario 1: Improved Levees	18-2
	18.2.1 Overview of Trial Scenario 1	18-2
	18.2.2 Evaluation of Trial Scenario 1	18-2
18.3	Trial Scenario 2: Through-Delta Conveyance (Armored Pathway)	18-5
	18.3.1 Overview of Trial Scenario 2	18-5
	18.3.2 Evaluation of Trial Scenario 2	18-5
18.4	Trial Scenario 3: Isolated Conveyance Facility	18-6
	18.4.1 Overview of Trial Scenario 3	18-6
	18.4.2 Evaluation of Trial Scenario 3	18-7
18.5	Trial Scenario 4: Dual Conveyance	18-8
	18.5.1 Overview of Trial Scenario 4	18-8
	18.5.2 Evaluation of Trial Scenario 4	18-8
Section 19	Results and Observations	19-1
19.1	Summary of Key Findings of Building Blocks	19-1
19.2	Evaluation of Building Blocks	19-9
19.3	Summary of Key Findings of the Scenarios	19-10
19.4	Conclusions	19-13
Section 20	Assumptions and Limitations.....	20-1
Section 21	References	21-1
Tables		
2-1	Summary of Building Blocks	
2-2	Summary of Building Blocks and Scenarios	
4-1	Summary of Suitable Materials	
4-2	Summary of Cost Estimate for PL 84-99 Upgrade – Option 1	
4-3	Summary of Cost Estimate for Urban Project Levee Upgrade	
4-4a	Summary of Cost Estimate for Setback Levee – Option 1	
4-4b	Summary of Cost Estimate for Setback Levee – Option 2	
5-1	Production Rates by Time (SRRQ and Others, Marine-Based)	
5-2	Enhanced Emergency Preparedness/Response Budgets	
6-1	Comparison of Primary Semi-Diurnal (M ₂) and Diurnal (K ₁) Tidal Constituents	
7-1	Short-Listed Islands for Carbon Sequestration Where Subsidence and Levee Fragility Are Greatest	
7-2	Potential Islands for Carbon Sequestration (Where Subsidence and Levee Fragility are Greatest and Asset Values are Minimized)	
7-3	Islands Selected for Assessment	

TABLE OF CONTENTS

7-4	Agricultural Land Use on Potential Islands for Carbon Sequestration
7-5	Infrastructure Assets on Potential Islands for Carbon Sequestration
7-6	Estimated Earthwork Required for Each Island Assuming an Overall 2-Foot Variation in Elevation
7-7	Carbon Credits Generated at Equilibrium for Short-Listed Delta Islands
7-8	Revenue Earned Through the Production of Carbon Credits
7-9	Estimated Net Value of Agricultural Production (\$/acre)
7-10	Estimated Value of Agricultural Production Foregone
7-11	Conceptual-Level Construction Cost Estimate for Short-Listed Islands
7-12	Operation and Maintenance Cost Estimate for Short-Listed Islands
7-13	Change in Subsidence with Carbon Sequestration
7-14	Island Subsidence With and Without Carbon Sequestration
8-1	Alignment Existing Features
8-2	Preliminary Cross-Section Dimensions
8-3	Improved Levee Locations and Lengths
8-4	Cost Estimate for Building Block 1.6, Armored Pathway Through Delta Conveyance
8A-1	Listed Riparian Species Depicted in Figures 8A-3 and 8A-4
8A-2	Vegetated Levee Planting Schedule
8A-3	Summary Cost Estimate for Self-Mitigating Vegetating of Set-back Levees
8A-4	Summary Cost Estimate for Simple Design for Vegetating Set-back Levees
9-1	Summary Cost of a 15,000 cfs ICF
9-2	Summary of Costs of the ICF Alternatives
9A-1	Terrestrial Listed Species Located Within the Vicinity fo the Isolated Conveyance Facility
9A-2	Fish Species in the Vicinity of the Isolated Conveyance Facility Intake
9A-3	Chinook Salmon Uses of Waters Affected by Isolated Conveyance Facility by ESU
9A-4	Chinook Salmon Seasonal Uses by ESU
9A-5	Fish Species Found in State Water Project Salvage
10-1	Current Linear Infrastructure
10-2	Current Nonlinear Infrastructure
10-3	San Joaquin River Flood Stages
10-4	San Joaquin River Historic Crests at Vernalis Station
10-5	Bypass Detention Capacities
10-6	Water Surface Elevations
10-7	Project Impacts
10-8	Sensitive Species
10-9	Invasive Fish Species

TABLE OF CONTENTS

10-10	Cost Estimates
11-1	Summary of Cost Estimates
12-1	Summary of Quantities
12-2	Armored Infrastructure Corridor: Cost Estimate Summary
13-1	List of Special Status Sensitive Species in Suisun Marsh
13-2	Key Agencies and Groups Managing Suisun Marsh
13-3	Significant Policies Affecting Marsh Actions
13-4	Suisun Marsh Existing Habitat Composition by Planning Region
13-5	Target Acreages for Tidal Restoration
13-6	Total Area and Levee Lengths for Conceptual Restoration Areas
13-7	Total Area and Planned Improvements in Conceptual Managed Wetland Enhancement Areas
13-8	Tidal Datum for Montezuma Slough at Suisun Slough Cut
13-9	Existing Elevations (LiDAR 2005)
13-10	Conceptual-Level Capital Costs of Building Block 3.1:Suisun Marsh Tidal Wetland Restoration
13B-1	Infrastructure and Assets in Suisun Marsh
13C-1	Levee Breach Cost Calculations
13C-2	Suisun Marsh Levee Specifications Standard
14-1	Restoration Sites Within, Adjoining, or Nearby the Restoration Area ^a
14-2	Restored Areas in the Yolo Bypass
14-3	Estimated Net Value of Agricultural Production (\$/acre)
14-4	Estimated Value of Agricultural Production Foregone
14-5	Conceptual-Level Cost Estimate Summary for the Tidal Marsh Cache Slough Restoration Alternative
14A-1	Data Sources, Methods, and Major Finding of Delta Smelt Sampling in the Cache Slough Area
14A-2	Presence of Delta Smelt Adult Life Stages in the Northern San Francisco Estuary (Spring Kodiak Trawl)
14A-3	Presence of Larval Delta Smelt as a percent of samples in Regions in the Northern San Francisco Estuary
14B-1	Listed Species in the Cache Slough Area
14B-2	Special Status Species in the Jepson Prairie-Prospect Island Corridor
14D-1	Area of Agricultural Land Use in the Cache Slough Restoration Area
14D-2	Value of Agricultural Production
14D-3	Assets and Total Asset Values in the Cache Slough Restoration Area
14E-1	Bird Species at Liberty Island (2005)

TABLE OF CONTENTS

14E-2	Fish Captured at Liberty Island (2005)
17-1	Effects on Urban and Agricultural Agencies of a Permanent Reduction in Export Supplies
17-2	Summary of Combined Water Exports (acre-feet) at the SWP and CVP Facilities Assumed in the Fish Salvage Estimates
17-3	Summary of the Change in Fish Salvage in Response to Reductions in SWP and CVP Exports
18-1	Scenario 1 Building Blocks
18-2a	Percent Reduction in Economic Costs and Impacts from Base Case under Seismic Events
18-2b	Percent Reduction in Economic Costs and Impacts from Base Case under Seismic Events
18-3	Percent Reduction in Economic Costs and Impacts from Base Case under Flood Events
18-4	Capital Costs of Implementation for Different Trial Scenarios
18-5	Risk Growth Factors for 2050 and 2100
18-6	Summary of Costs and Benefits of Trial Scenarios
18-7	Building Blocks for Trial Scenario 2
18-8	Scenario 3 – Isolated Conveyance Facility
18-9	Scenario 4 – Dual Conveyance
19-1	Building Block Evaluation Summary
19-2	Scenario Evaluation Summary

Figures

1-1	Program Functional Organization
3-1	Building Block 1.1: Improved Levee Maintenance
3-2	Levee Failure Rate
4-1	Building Block 1.2: Upgraded Delta Levees Upgrade 764 miles of Delta Levees to PL 84-99 Standards
4-2	Building Block 1.2: Upgraded Delta Levees Upgrade 187 miles of Delta Levees to Urban Project Levee Standards
4-3	Typical Cross Section PL 84-99 Standards
4-4	Typical Cross Section Urban Project Levee (UPL) Standards
4-5a-e	Parametric Cross Section PL 84-99 Standards
4-6a-e	Parametric Cross Section Urban Project Levee (UPL) Standards

TABLE OF CONTENTS

5-1	Potential Delta Area Emergency Materials Stockpile and Transshipment Sites
5-2	Building Block 1.3 Enhanced Emergency Preparedness/Response
5-3	Material Supply Rates by Time after Event (SRRQ and Others, Marine-Based)
5-4	South Delta Pathway Levees, Adjoining Channel Barriers and North Delta Channel Closures
6-1	Building Block 1.4 Pre-Flooding of Selected Western Islands
6-2	Set 1: Western islands – Sherman, Jersey, Bradford, Twitchell, Brannon-Andrus
6-3	Set 2: Eastern Islands – Venice, Mandeville, MacDonald, Jones, Bouldin
6-4	Set 3: Southern Islands – Palm-Orwood, Bacon, Woodruff, Jones, Victoria
6-5	Set 4: 20 Islands
6-6	RMA Bay Delta Model Finite Element Geometry with 20 Delta Islands
6-7	RMA Bay Delta Model Island Breach Locations and Lengths
6-8	Total Inflow, Total Export, and Net Delta Outflow estimate from Dayflow
6-9	Delta Monitoring Stations for comparison of computed and observed EC
6-10	Comparison of Observed and Simulated Base Case tidally averaged EC at RSAC075 (Chipps Island)
6-11	Comparison of Observed and Simulated Base Case tidally averaged EC at RSAN018 (Jersey Point)
6-12	Comparison of Observed and Simulated Base Case tidally averaged EC at RSAN032
6-13	Comparison of Observed and Simulated Base Case tidally averaged EC at ROLD024
6-14	Comparison of Observed and Simulated Base Case tidally averaged EC at SWP Intake
6-15	M2 and K1 Amplitude, Base Case
6-16	M2 and K1 Amplitude, Set 1: Western Islands
6-17	M2 and K1 Amplitude, Set 3: Eastern Islands
6-18	M2 and K1 Amplitude, Set 3: Southern Islands
6-19	M2 and K1 Amplitude, Set 4: 20 Islands
6-20	Tidal Flow at Martinez
6-21	Tidal Flow at Chipps Island
6-22	EC Time Series Locations for Comparison of Pre-Flooded Island Sets
6-23	Comparison of Instantaneous and Tidally Averaged EC Time Series for Pre-Flooded Island Sets at RSAC075
6-24	Comparison of Instantaneous and Tidally Averaged EC Time Series for Pre-Flooded Island Sets at RSAN018

TABLE OF CONTENTS

6-25	Comparison of Instantaneous and Tidally Averaged EC Time Series for Pre-Flooded Island Sets at RSAN032
6-26	Comparison of Instantaneous and Tidally Averaged EC Time Series for Pre-Flooded Island Sets at ROLD024
6-27	Comparison of Instantaneous and Tidally Averaged EC Time Series for Pre-Flooded Island Sets at RMID015
6-28	Comparison of Instantaneous and Tidally Averaged EC Time Series for Pre-Flooded Island Sets at State Water Project Intake
6-29	EC Contours on October 31, 2002 and May 31, 2003 – Base Simulation
6-30	EC Contours on October 31, 2002 and May 31, 2003 – Set 1: Western Islands
6-31	EC Contours on October 31, 2002 and May 31, 2003 – Set 2: Eastern Islands
6-32	EC Contours on October 31, 2002 and May 31, 2003 – Set 3: Southern Islands
6-33	EC Contours on October 31, 2002 and May 31, 2003 – Set 4: 20 Islands
6-34	Comparison of Tidally Averaged EC for Pre-Flooded Island Set 1 with varying Net Delta Outflow at RSAC075
6-35	Comparison of Tidally Averaged EC for Pre-Flooded Island Set 1 with varying Net Delta Outflow at RSAN018
6-36	Comparison of Tidally Averaged EC for Pre-Flooded Island Set 1 with varying Net Delta Outflow at RSAN032
6-37	Comparison of Tidally Averaged EC for Pre-Flooded Island Set 1 with varying Net Delta Outflow at ROLD024
6-38	Comparison of Tidally Averaged EC for Pre-Flooded Island Set 1 with varying Net Delta Outflow at RMID015
6-39	Comparison of Tidally Averaged EC for Pre-Flooded Island Set 1 with varying Net Delta Outflow at State Water Project Intake
6-40	CALSIM Base Net Delta Outflow and Total Exports for Breach Event Start Times
6-41	Number of Days to Resume Export Pumping, 20-Island Levee Failure Event
6-42	Export Deficit when Pumping is Resumed, 20-Island Levee Failure Event
7-1	Building Block 1.5: Land Use Changes to Reduce Island Subsidence
7-2	Predicted subsidence in the Delta for 2100
7-3	Carbon accumulation over time in a continuously flooded wetland
7-4	Biochemical Processes in Wetlands
7-5	Decomposition of organic matter under aerobic and anaerobic (flooded) conditions
8-1	Building Block 1.6: Armored Pathway” Through Delta Conveyance
8-2	Historical Flows in the Sacramento River

TABLE OF CONTENTS

8-3	Seismic-Resistant Setback Levees
8-4	Location Map of Proposed Intake Facility
8-5	Redlands Canal Fish Screen (Courtesy USFWS)
8-6	Redlands Canal Fish Screen (Courtesy USFWS)
8-7	Delta Cross Channel Radial Arm Gates (Courtesy USBR)
8-8	Preliminary Corridor Cross Section
8-9	Inflatable Barrier Gate
8A-1	Historical Distribution of Riparian Vegetation
8A-2	Riparian Zone Habitats Utilized by Bird Species
8A-3a	Species Whose Populations Would Be Connected by Setback Levee Corridor: Plants
8A-3b	Species Whose Populations Would Be Connected by Setback Levee Corridor: Wildlife
8A-4a	Species Whose Habitat Area Would Be Increased by Setback Levee Corridor: Plants
8A-4b	Species Whose Habitat Area Would Be Increased by Setback Levee Corridor: Wildlife
9-1	Building Block 1.7: Isolated Conveyance Facility Alternatives
9-2	Isolated Conveyance Facility Routes 1 and 2
9-3	Isolated Conveyance Facility Route 2 Profile – Midstream
9-4	Historical Flows in the Sacramento and San Joaquin Rivers
9-5	Soils in the North Delta
9-6	Soils in the South Delta
9-7	Thickness of Organics
9-8	Canal Cross Section
9-9	Typical Siphon Plan and Profile
9A-1	Isolated Conveyance Facility Impacts to Ecosystem
10-1	Building Block 1.8: San Joaquin Bypass (Alt 1)
10-2	Building Block 1.8: San Joaquin Bypass (Alt 2)
10-3	San Joaquin Bypass: Alternative 1, Detention & Bypass
10-4	San Joaquin Bypass: Alternative 2, 0.5-mile widening
10-5	River Cross Section Locations
10-6	Comparison of Current to Widened Cross Section (Mean Higher High Water Indicative of Potential Floodplain Habitat Type)
10-7	Water Surface Elevation in the San Joaquin River for San Joaquin River Bypass Alternatives for January 1997 Storm event

TABLE OF CONTENTS

10-8	Water Surface Elevation in the San Joaquin River for San Joaquin River Bypass Alternatives for April 2006 Storm Event
10-9	Water Surface Elevation in the San Joaquin River for San Joaquin River Bypass Alternatives for February 1998 Storm Event
10-10	Water Surface Elevation in the San Joaquin River for San Joaquin River Bypass Alternatives for January 1969 Storm Event
11-1	Building Block 2,1: Raise State Highways
11-2	Limits of Improvements on SR 4, SR 12, and SR 160
11-3	Layout of Realigned SR 160
11-4	Photo of I-80 at Yolo Bypass
11-5	Typical Cross Section of the Elevated Structure
11-6	Photos of Drawbridges in the Sacramento Delta
12-1	Building Block 2.2, Armored Infrastructure Corridor
12-2	Existing Infrastructure and Limits of New Levees
12-3a	Layout of Armored Infrastructure Corridor, Option 1
12-3b	Layout of Armored Infrastructure Corridor, Option 2
12-4a	Typical Cross Section of Armored Infrastructure Corridor, Option 1
12-4b	Typical Cross Section of Armored Infrastructure Corridor, Option 2
13-1	Building Block 3.1: Tidal Wetlands Restoration and Managed Wetland Enhancements in Suisun Marsh
13-2	Suisun Marsh Region
13-3	Historic Map Suisun Bay region (circa 1902-1908)
13-4	Suisun Marsh Region Existing Conditions
13-5	Suisun Marsh Planning Regions
13-6	Water Control Structures in Suisun Marsh
13-7	Areas in Suisun Marsh Flooded by Screened Diversions
13-8	Location of Abandoned, New and Upgraded Levees in Conceptual Restoration Areas
13-9	Location of Abandoned, New and Upgraded Levees in Conceptual Managed Wetland Enhancement Areas
13A-1	Parametric Cross Section Suisun Marsh Levee Specification – Levee Upgrade
13A-2	Parametric Cross Section Suisun Marsh Levee Specification – New Levee
14-1	Building Block 3.2: Tidal Marsh Cache Slough Restoration Alternative
14-2	Cache Slough and Yolo Bypass (1903-1910)
14-3	Tidal Marsh Cache Slough Restoration Alternative Project Area
14A-1	Spring Kodiak Trawl Sampling Stations
14A-2	20-mm Survey Sampling Stations
14C-1	Yolo Bypass
15-1	Building Block 3.3: Install Fish Screens

TABLE OF CONTENTS

16-1	Building Block 3
17-1	Building Block 3.6: Reduce Water Exports from the Delta
17-2a	SWP and CVP Exports WY 2000 – Above Normal Year Preceded by Wet Year
17-2b	SWP and CVP Exports WY 1994 – Critical Year Preceded by Above Normal Year
17-3a	Monthly Water Exports with Reductions – Normal or Wet Years – Water Year 2000 as Example (Above Normal Year Preceded by Wet Year)
17-3b	Monthly Water Exports with Reductions – Dry or Critical Years – Water Year 1994 as Example (Critical Year Preceded by Above Normal Year)
17-4a	Percent Reduction in Fish Salvage for Various Reductions in Delta Exports Wet or Normal Year – Water Year 2000 as an Example
17-4b	Percent Reduction in Fish Salvage for Various Reductions in Delta Exports Dry or Critical Year – Water Year 1994 as an Example
18-1	Trial Scenario 1 – Improved Levees
18-2	Expected Economic Costs of Trial Scenarios at Different Years
18-3	Expected Economic Impacts (Value of Lost Output) of Trial Scenarios at Different Years
18-4	Scenario 2 Through-Delta Conveyance
18-5	Trial Scenario 3 – Isolated Conveyance Facility
18-6	Trial Scenario 4 – Dual Conveyance

Appendices

5A	Combination Sheet Pile Wall Examples
5B	Channel Barrier Concepts
8A	Environmental Impact of Armored Pathway
9A	Ecosystem Impacts of Building Block 1.7: Isolated Conveyance Facility Alternatives
9B	Preliminary Cost Estimate for 15,000 cfs Isolated Conveyance Facility
11A	Comparative Bridge Costs
13A	Levee Cross Sections: Suisun Marsh Levee Specifications
13B	Value of Infrastructure and Assets in Conceptual Restoration Areas
13C	Cost Calculations
14A	Delta Smelt in the Cache Slough Area
14B	Listed Species in the Cache Slough Area
14C	Function of the Yolo Bypass
14D	Assets in the Cache Slough Area
14E	Species Found at Liberty Island (2005)

TABLE OF CONTENTS

Attachments

8A-1 Riparian Plants for Birds

Boxes

13-1 Suisun Marsh Tidal Wetland Restoration and Managed Wetland Enhancement Building Block Flashcard

13-2 Goals of the Habitat Management, Preservation, and Restoration Plan for the Suisun Marsh

Acronyms

ACOE	U.S. Army Corps of Engineers
BAU	business as usual
BCDC	San Francisco Bay Conservation and Development Commission.
BDCP	Bay Delta Conservation Plan
BNSF	Burlington National Santa Fe
BREACH	Sacramento/San Joaquin Delta Breached Levee Wetland Study
CALFED	California Bay-Delta Authority
CALSIM	California Water Resources Simulation Model
CALVIN	California Value Integrated Network Model
CCF	Clifton Court Forebay
CDFG	California Department of Fish and Game
CE	Conservation Easement
CESA	California State Endangered Species Act
cfs	cubic feet per second
CH ₄	methane
CNDDB	California Natural Diversity Database
CNLM	Center for Natural Lands Management
CNPS	California Native Plant Society
CO ₂	carbon dioxide
CO ₂ e	carbon dioxide equivalents
CSC	Candidate Species of Concern
CVJV	Central Valley Joint Venture
CVP	Central Valley Project
cy	cubic yard
DCC	Delta Cross Channel

TABLE OF CONTENTS

DICU	Delta Island Consumptive Use
DMC	Delta-Mendota Canal
DOC	dissolved organic carbon
DOM	dissolved organic material
DP	shrub container size
DPS	distinct population segment
DRMS	Delta Risk Management Strategy
DWR	California Department of Water Resources
DWSC	Sacramento River Deep-Water Ship Channel
ea	each
EBMUD	East Bay Municipal Utilities District
EC	electrical conductivity
ECAT	Environmental Coordination and Advisory Team
EFH	Essential Fish Habitat
EOP	Emergency Operation Plan
ERP	Ecosystem Restoration Program
ERPP	Ecosystem Restoration Program Plan
ER&R	Emergency Response and Repair
FEMA	Federal Emergency Management Agency
FESA	Federal Endangered Species Act
FIRM	Federal Insurance Rate Map
fps	feet per second
ft	foot (feet)
GHG	greenhouse gases
GIS	Geographic Information System
H:V	horizontal to vertical ratio
Hg	mercury
HMP	Hazard Mitigation Program
HRG	Habitat Restoration Group
I-5	Interstate 5
ICF	Isolated Conveyance Facility
IEP	Interagency Ecological Program

TABLE OF CONTENTS

IFSAR	Interferometric Synthetic Aperture Radar
JESFF	J. E. Skinner Fish Facility
JS	Jones and Stokes, Inc.
JSA	Jones and Stokes Associates, Inc.
kg	kilogram
kV	kilovolt
LiDAR	Light Detecting and Ranging
MAF	million acre-feet
Marsh	Suisun Marsh
MeHg	methylmercury
MHHW	mean higher high water
MLLW	mean lower low water
mm	millimeters
MWD	Metropolitan Water District of Southern California
NAVD88	North American Vertical Datum of 1988
NAWMP	North American Waterfowl Management Plan
NBA	North Bay Aqueduct
NDNWR	North Delta National Wildlife Refuge
NDO	Net Delta Outflow
NMFS	National Marine Fisheries Service
NO ₂	nitrous oxide
NOAA	National Oceanic and Atmospheric Administration
NPV	net present value
NRCS	Natural Resources Conservation Service (a division of the USDA)
O.C.	On Center – refers to distances along the length of the river.
OGSC	Office of the Governor of the State of California
O&M	operation and maintenance
PC/PS	pre-cast, pre-stressed
PEIR/EIS	Programmatic Environmental Impact Report/Environmental Impact Statement
PFC	Pacific Flyway Council
PG&E	Pacific Gas and Electric Company
PL	Public Law

TABLE OF CONTENTS

PRBO	Point Reyes Bird Observatory
PWA	Philip Williams and Associates, Ltd.
RMA	Resource Management Associates
SAV	submerged aquatic vegetation
SEMS	Standardized Emergency Response System
SLT	Solano Land Trust
SMPA	Suisun Marsh Preservation Agreement
SOD	south of Delta
SPT	Standard Penetration Test
SRA	Shaded Riverine Habitat
SRCD	Suisun Resource Conservation District
SRRQ	San Rafael Rock Quarry
SWP	State Water Project
SWRCB	State Water Resources Control Board
TFF	Tracy Fish Facility
TOC	total organic content
TPL	Trust for Public Lands
UCS	Uniform Classification System
umhos/cm	micro-mhos per centimeter
UPL	Urban Project Levees
URS	URS Corporation
USACE	U.S. Army Corps of Engineers
USBR	U.S. Bureau of Reclamation
USDA	United States Department of Agriculture
USFWS	U.S. Fish and Wildlife Service
XS	cross section
WAM	Water Analysis Module
WGI	Washington Group International
WRP	Wetland Reserve Program
WSE	water surface elevation
YBF	Yolo Basin Foundation
YBWG	Yolo Bypass Working Group

TABLE OF CONTENTS

Definitions

Listed Species

A species which is a species which is listed as Federally Endangered, Federally Threatened, Federal Candidate species, California State Endangered, California State Threatened, California State Rare, California Department of Fish and Game (DFG) Species of Concern, California Native Plant Society Species Rare/Endangered in CA or elsewhere, California Native Plant Society Species Rare/Endangered in California and more common elsewhere.

Federally Listed Species

Under the Federal Endangered Species Act (FESA), the Secretary of the Interior and the Secretary of Commerce jointly have the authority to list a species as endangered or threatened. FESA defines “endangered” species as any species in danger of extinction throughout all or a significant portion of its range. A “threatened” species is any species that is likely to become an “endangered” species within the foreseeable future throughout all or a significant portion of its range. Additional special-status species include “candidate” species and “species of concern.” “Candidate” species are those for which the U.S. Fish and Wildlife Service (USFWS) has enough information on file to propose listing as endangered or threatened. “Species of concern” are those for which listing is possibly appropriate but for which the USFWS lacks sufficient information to support a listing proposal. A species that has been “delisted” is one whose population has met its recovery goal target and is no longer in jeopardy of extinction.

California State Listed Species

Section 2080 of the California Endangered Species Act (CESA) prohibits the “take” of state-listed threatened and endangered species. The CESA defines take as any action or attempt to hunt, pursue, catch, capture, or kill any listed species. If a proposed project may result in “take” of a listed species, a permit pursuant to Section 2080 of CESA is required from the California Department of Fish and Game (DFG). Take of state-listed species is authorized through Section 2081 through a permit process. Take can also be authorized through Section 2835 with an approved Natural Community Conservation Plan.

DFG

The DFG also designates “fully protected” or “protected” species as those that may not be taken or possessed without a permit from the Fish and Game Commission and/or the DFG. Species designated as fully protected or protected may or may not be listed as endangered or threatened.

Additional Protection:

Migratory Birds

The federal Migratory Bird Treaty Act (16 USC §703, Supp. I, 1989) prohibits killing, possessing, or trading in migratory birds except in accordance with regulations prescribed by the Secretary of the Interior. This act encompasses whole birds, parts of birds, bird nests, and eggs. Disturbance during the breeding season could result in the incidental loss of fertile eggs or nestlings, or otherwise lead to nest abandonment, and violate the Migratory Bird Treaty Act.

TABLE OF CONTENTS

Wetlands

Executive Order 11990 requires federal agencies to take action to minimize the destruction or modification of wetlands by considering both direct and indirect impacts to wetlands that may result from federally funded actions.

Invasive Species

Under Executive Order 13112, projects that occur on federal lands or are federally funded must “subject to the availability of appropriations, and within administration budgetary limits,” use relevant programs and authorities to (i) prevent the introduction of invasive species; (ii) detect and respond rapidly to, and control, populations of such species in a cost-effective and environmentally sound manner; (iii) monitor invasive species populations accurately and reliably; and (iv) provide for restoration of native species and habitat conditions in ecosystems that have been invaded.”